

## **Targhee Breaker Installation and Yard Expansion**

The purpose of this project is to reduce outages at Targhee Substation and expand the substation yard to accommodate future Phase 2 line terminal. This project will remove the existing disconnect at Targhee Substation and replace it with a new Power Circuit Breaker package including protective relays. Further, the yard will be expanded to enable a standard breaker layout and enable future substation additions without re-work. Any faults on the Swan Valley – Teton #1 or Targhee tap lines cause outages at Targhee Substation.